21st October 1927]

A list of villages benefited by the scheme is herewith forwarded.

List of villages benefited by the Gundlakamma Project up to 30 miles 6 furlongs 638 feet of main canal.

1. Timmayapalem.
2. Kotigalapudi (Darsi taluk, Nellore district).
3. Timmayareddipalem.
4. Nennurpad.
5. Dhenuvakonda.
6. Periapalem.
7. Garlapad.
8. Gadiuapudi.
9. Doddavaram.
10. Tellapad.
11. Mallavaram.
12. Kolachinakota.
13. Velampalli.
14. Maddipad.
15. Nandipad.
16. Inamanamellur.
17. Maddiralapad.
18. Doddavarapad.
19. Edukundlapad.
20. Chekurupad.

APPENDIX VII.

[Vide answer to question No. 787 asked by Mr. Sami Venkatachalam Chetti at the meeting of the Legislative Council held on the 21st October 1927, page 328 supra]

Comparative statement of discharge of the Musi River at Pulikonda, 1922 to 1924 (Gauge No. 1).

Gauge height in feet.	1922. Discharge (cusecs).			Discharge 1923.	Discharge 1924.
	Up to 7th November 1922.	8th to 11th November 1922 and 22nd November 1922 to 26th November 1922.	12th November 1922 to 22nd November 1922.		
(1)	(2)	(3)	(4)	(5)	(6)
0·50	3	..	67	23	51
0·60	9	64	95	37	78
0·70	22	90	131	53	118
0·80	41	119	172	71	170
0·90	64	153	221	90	230
1·00	92	193	282	114	307
1·10	124	241	350	139	388
1·20	160	294	434	167	470
1·30	198	355	530	198	560
1·40	239	424	642	234	660
1·50	285	502	760	274	766
1·60	335	590	875	327	876
2·00	578	1,230	1,460	..	..
2·50	..	2,190	2,280	..	..
3·00	..	3,150	3,160	..	..
3·50	..	..	4,120	..	..
4·00	..	..	5,170	..	..
4·50	..	..	6,300	..	..
5·00	..	..	7,530	..	..
5·50	..	..	8,900	..	..
6·00	..	..	10,400	..	..
6·50	..	..	12,100	..	..
7·00	..	..	14,110	..	..
7·50	..	..	16,390	..	..